

PROSURFACE INC.

Phone: (714)348-6427

PO Box 80878, Rancho Santa Margarita CA 92688

www.ProSurface.net

September 17, 2020

Reference: Tennis Court Resurfacing at La Sierra High School, in Riverside (8 tennis courts)
Attn: Adonna Calderon, Program Manager, Administrative Services

Per your request, I am pleased to present the following proposal for the repairs and resurfacing of eight (8) tennis courts for La Sierra High School, in Riverside. The following outline generally describes the steps required to restore the courts.

SURFACE/CONCRETE PREPARATION

- 1) SURFACE REMOVAL- The courts will be checked for existing non-bonded surface areas. These areas will be Diamond Grinded to remove the existing paint coatings and provide the necessary surface for the acrylic surfacing system. The excess court dust/debris will be contained by an OSHA compliant high-volume vacuum. The majority of this phase is required on the four south side courts, and along the sides of all cracks on the eight courts.
- 2) DIAMOND GRINDING- The worn and exposed concrete baselines and surface areas will be Diamond Grinded to "etch" the concrete, providing a surface for proper adherence of the acrylic surface materials.
- 3) CAULKING INSTALLATION (optional)- 1108' linear feet of caulking, between the courts and under the net lines, will be removed. The expansion joints will be grinded and cleaned. Sika 2CSL caulking material will be installed into the joint areas.
- 4) WASH/SURFACE PREP- The courts will be washed and/or floor sanded to provide the necessary surface for the installation of the surfacing system.

SURFACE COATINGS

- 5) PRIMER- All exposed concrete will be primed to provide proper adherence of the color surface coatings.
- 6) ACRYLIC RESURFACER COATINGS (with Color Plus tint) - Two (2) SportMaster Acrylic Resurfacer coatings with 60/90-grit silica sand shall be applied to each court. The AR yield will be a minimum of .07 gallons of undiluted material per square yard. The material will be tinted with ColorPlus to the color scheme choice per owner's request. Colors: Forest Green interiors/Red exteriors.
- 7) FINISH COAT- The final SportMaster acrylic Color Concentrate sand coat shall be applied to the courts. The Color Concentrate yield will be .05 gallons of undiluted material per square yard. #90 "Scott" silica sand shall be mixed to the color material in grades and amounts as required to provide a finish surface with a standard, medium/ slow, playing speed.

LINES

- 8) LINING OF COURTS- The court lines shall be measured to U.S.T.A. specifications. The line areas shall be taped, sealed and rolled with white textured acrylic line paint per manufactures specs. 2" standard lines with 3" baselines.

9) CLEAN UP- After all work is completed; the entire work area shall be left in a neat, clean and useable condition.

THE PRICE FOR THE WORK AS DESCRIBED IS.....\$88,523.00 Total

Cost Breakdown-

Surface Removal/Diamond Grinding	\$ 8,770.00
SportMaster Surfacing System, \$6,900.00 per court x 8	\$55,200.00
-Additional work/items included in Project Total:	
Caulking installation at expansion joints, \$7.00 per ft x 1108' linear ft.	\$ 7,756.00
706' linear ft. Polypropylene "Open Mesh" Windscreen	\$12,797.00
15' Vinyl panels (2) w/ "EAGLES" + logo. \$800.00 ea.	\$ 1,600.00
New Tennis Nets w/ Double Reinforced Top, \$300.00 ea.	\$ 2,400.00

All work shall be in accordance with manufacturer's specifications. We use the finest products offered by the industry to ensure custom performance. As a licensed contractor in The State of California, we carry the required workers compensation and insurance. We take pride in the quality of our work and we have several qualified references available upon request. We thank you for the opportunity to quote you on this project and we look forward to speaking with you again soon.

Respectfully submitted,

Jeff Frantz
President

TERMS AND CONDITIONS

-Price subject to change if not accepted within 30 days.

-Prices do not include testing, permits, inspections or engineering costs.

-Payment request: 50% for custom materials order. 50% upon completion.

-Any invoice not paid in 30 days is subject to 1.5% service charge per month. (Unless otherwise determined by both parties).

-Foundation blemishing and structural conditions such as cracking, chipping, peeling/bubbling may not be permanently eliminated and cannot be guaranteed. Cracking will reoccur. Structural blemishes are result of the foundation and cannot be guaranteed. Scheduled court resurfacing/maintenance may help to contain courts imperfections, but will not permanently correct foundation blemishing.

-ASR conditions may immediately reoccur. In some cases, the proposed steps may help to slow the reoccurring process, but will not guarantee complete elimination of the ASR.

-Surface installation will not change the slope or pitch of the concrete. Court resurfacing is primarily to provide a playable court speed and a cosmetically attractive and safe playing surface.

-Court repairs and resurfacing will be completed in a timely matter, with reasonable weather.

Acceptance of Proposal:

The above prices, specifications and conditions are satisfactory and are hereby accepted. ProSurface is authorized to do the work as specified.

Signature _____ Date of Acceptance _____