

NEW DIMENSION

general construction, inc.

License 865303
office 714.492.5929
719.5 Monroe Way, Placentia, CA 92870

Proposal

Dir Reg # 1000003878

Date	Estimate #
12/3/2020	3909v3

Name / Address
Alvord USD 10365 Keller Ave Riverside, Ca 92505

Location
6585 Crest Ave, Riverside Norte Vista High

Description	Qty	Cost	Total
Material and Labor Supplied by New Dimension to labor and material supplied to pressure wash entire campus. Includes walls, awnings, over hangs, and exterior of windows. Note: Does not include roofs. Does not include swepps, erosion control, or water recycling systems.	1	69,767.01	69,767.01
Material and Labor Supplied by New Dimension to demo approximately 1560 LF of 24" tall sun shade off first story buildings. Grind welds for smooth finish. Includes haul off.	1	19,463.54	19,463.54
Material and Labor Supplied by New Dimension to prep and repair mastic around misc. storefront glass panels	1	19,463.54	19,463.54
Material and Labor Supplied by New Dimension to replace existing upblast wall vent at gym with new unit.	1	1,453.28	1,453.28
Material and Labor Supplied by New Dimension to Remove and replace all weatherstripping at all doors throughout campus. Approximately 150 doors total.	1	25,223.71	25,223.71
		Total	

Acceptance Signature

Date

NEW DIMENSION general construction, inc.

License 865303
office 714.492.5929
719.5 Monroe Way, Placentia, CA 92870

Proposal

Dir Reg # 1000003878

Date	Estimate #
12/3/2020	3909v3

Name / Address
<p>Alvord USD 10365 Keller Ave Riverside, Ca 92505</p>

Location
<p>6585 Crest Ave, Riverside Norte Vista High</p>

Description	Qty	Cost	Total
<p>Material and Labor Supplied by New Dimension to</p> <ul style="list-style-type: none"> • Mask and protect areas that are not to receive finishes • Sand and scrape off delaminating paint throughout areas • Prep and patch small hairline line cracks at walls • Prime walls and soffits as needed • Paint walls and soffits with two coats of paint – paint finish to be 100% flat acrylic – see provided spec • Stain main entry walls and benches and concrete benches as per job walk • Prep, sand, prime as needed and paint doors, frames and roll up doors • Prep, sand, prime as needed and paint under side of canopies at walkway areas and all canopies throughout • Prep, and paint columns and beams at canopies walkway areas • Prep and paint dropdowns, gutters and flashing cap • Paint canopy/overhang and beams at Performance Arts Center and Gymnasium areas • Paint hollow metal window frames • Paint Light poles throughout campus • Clean up areas as completed per section <p>Painting of exterior walls – includes Performance Art center, Gymnasium Building, all classroom buildings, snack bars, ticket booth, trailer classroom types, restroom and exterior pool walls</p> <p>Paint Cost Alternates:</p> <p>Add county building to scope. Add cost \$20,480.92</p> <p>Paint walls and ceilings at baseball dugouts QTY 2. Add cost \$6,860.75</p> <p>Prep and paint concrete floors at dug outs QTY 2 (one coat of AMERLOC/primer coat and one coat of AMERSHIELD top coat). \$5,752.48</p> <p>Paint exterior walls and broadcast room/stadium. \$5,805.25</p> <p>Paint light poles throughout campus. \$10,080.03</p> <p>Paint railings, bollards, trash and mechanical enclosure gates. Includes painting of wrought iron at top of property walls (throughout campus). \$31,137.25</p>	1	773,271.16	773,271.16
		Total	\$908,642.24...

Acceptance Signature

Date