

# NEW DIMENSION

*general construction, inc.*

License 865303  
office 714.492.5929  
719.5 Monroe Way, Placentia, CA 92870

## Proposal

Dir Reg #  
PW-LR-1000776287

Date	Estimate #
4/19/2022	4391

Name / Address
Alvord USD 10365 Keller Ave Riverside, Ca 92505

Location
La Sierra High 4145 La Sierra Ave, Riverside, CA 92505 Culinary Arts Lab Building

Description	Qty	Cost	Total
Material and Labor Supplied by New Dimension to sawcut and demo approximately 3200 sqft of existing 6" concrete slab flatwork. Includes haul off and disposal.	1	12,648.85	12,648.85
Material and Labor Supplied by New Dimension to Dig up and haul off 40 cubic yards of native soils to make room for added CMB layer.	1	6,798.46	6,798.46
Material and Labor Supplied by New Dimension to Compact native to 95% throughout area. Import 40 cubic yards of CMB for a 4" rock layer throughout area. Compact to 95%. Install 6mil visquene vapor barrier.	1	8,432.25	8,432.25
Material and Labor Supplied by New Dimension to Form as needed for expansion joint layout shown on plans. Add #4 rebar 18" on center each way throughout area.	1	10,282.92	10,282.92
Material and Labor Supplied by New Dimension to Pour QTY 7 pads on day one. Slip joint dowels and sleeves to be used at expansion joints. Pull E.J. forms and pour remaining pads on day 2.	1	21,518.84	21,518.84
Notes: -Concrete to be 3500PSI P-gravel. Medium broom finish. Control and expansion joints to be set per plans. Control joints to be wet troweled. -Work to be done during normal business hours. -Cost of Bonding is Included.			
		<b>Total</b>	\$59,681.32

Acceptance Signature

Date

\_\_\_\_\_

\_\_\_\_\_/\_\_\_\_\_/\_\_\_\_\_