

# NEW DIMENSION

*general construction, inc.*

License 865303  
office 714.492.5929  
719.5 Monroe Way, Placentia, CA 92870

## Proposal

Dir Reg #  
PW-LR-1000776287

Date	Estimate #
5/2/2022	4392v2

Name / Address
Alvord USD 9 KPC Parkway Corona, CA 92879

Location
Myra Linn Elementary School 10435 Branigan Way Riverside, CA 92505

Description	Qty	Cost	Total
Material and Labor Supplied by New Dimension to install chain link fencing and gates		0.00	0.00
WALKWAY REPAIR:		0.00	0.00
Material and Labor Supplied by New Dimension to: 1. remove and replace a 48ft long x 8'6" wide section of flatwork. Clean up and haul off 2. recompact area. Form, and install #3 rebar pins every 18" OC at existing flatwork joints. Add new #3 rebar throughout area every 18" OC each way. 3. Pour new 3500 PSI P-gravel concrete. Finish to match existing. Pull forms and cleanup 4. Re-stripe door swing arches, and re-install hold open pins as needed.			
CONCRETE WALKWAY		0.00	0.00
Material and Labor Supplied by New Dimension to: 1. cut 6" below existing grade at 53' long x 3' wide section as specified. 2. Compact area. Form and install #3 rebar pins every 18" OC into existing impacted flatwork. Add #3 rebar every 18" OC each way throughout flatwork. 3. Pour new 3500 PSI P-gravel concrete. Finish to match existing. Pull forms and cleanup. Backfill native soil against new flatwork edges.			
KINDER PLAYGROUND STRUCTURE		0.00	0.00
Material and Labor Supplied by New Dimension to remove existing monkeybar rings and ladder.			
GRAND TOTAL	1	52,753.94	52,753.94
OPTIONAL COST	1	6,021.17	6,021.17
Material and Labor Supplied by New Dimension to demo interior wall up to 10ft to length of interior room. Patch impacted areas. Install new VCT flooring in impacted area. ADD \$6,000.00 TO PROPOSAL			
		<b>Total</b>	\$58,775.11...

Acceptance Signature

Date

\_\_\_\_\_

\_\_\_\_\_/\_\_\_\_\_/\_\_\_\_\_