

BID ANALYSIS & RECOMMENDATION

Project Name: Relocation of portable from Northwood to West Park	Request Date: 7/8/19
Project Number: 7070	DSA #:
Requestor: Tracy Frye	
Service Requested: Provide and install underground conduit for power, data, signal & fire alarm from first portable on the south end of campus	

CONTRACTOR NAME:	QUOTE \$:	Pre-Qual (Y/N):
Napa Electric	\$36,400	Y

Recommendation Summary

Napa Electric is a long standing partner with the District and does quality work, their rates are favorable and within industry standards \$36,400

Requested NTP Date:

Required Attachments:

- ☒ Submitted Quotes
- ☒ RFP Documents
- ☒ Signed Request Public Works or Services

Approved and Reviewed by:

Signature: Kelli Jurgenson Digitally signed by Kelli Jurgenson
DN: C=US, E=kelli@vpcsonline.com, O=VPCS, CN=Kelli Jurgenson
Reason: I have reviewed this document
Date: 2019.07.27 15:24:07-0700 _____ **Date** _____
Bond Program Manager

For Accounting and Purchasing use only:

Budget Account / Sourcing:

25-9010-0-0000-8500-XXXX-977-7070	\$36,400.00
	\$0.00
	\$0.00
	\$0.00
TOTAL:	\$36,400.00

Approved and Reviewed by:

Signature: _____ **Date** _____
Bond Financial Analyst

Signature: _____ **Date** _____
Executive Director, Facilities, Maintenance & Operations



PO Box 818 • Napa, CA 94559 • State Lic # 214940 • Telephone: (707) 252-6611 • Fax: (707) 252-4960

Proposal Date: July 11, 2019

Effective To: August 11, 2019

Page 1 **of** 1

PROJECT PROPOSAL

Name of Project: West Park Portable

Location: Napa, CA

To: NVUSD

Phone:

Fax:

Attn: Tracy Frye

DESCRIPTION OF WORK

We are pleased to offer the following quote to the above referenced project:

- Provide and install underground conduit for power, data, signal and fire alarm from first portable.
- Provide Install new FA devices, 2-smoke detectors, 2-heat detectors, 1-wall mount speaker strobe and one outdoor speaker.
- Provide four data outlets with one data outlet at ceiling for wireless access point. (WAP provided by NVUSD)
- Extend existing speaker circuit from portable to new portable. (Speaker provided by NVUSD)
- Connect power to existing panel 400a Distribution panel with new 150amp breaker to feed portable.
- Provide and install grounding per district standard.
- Trench and backfill from first portable to new portable included.
- Disconnect utilities from existing portable at Northwood

Total Installed Price \$ 36,400

Clarifications:

- We exclude permit, plans, PG&E fees, and bonding.
- Work is to be completed during normal working hours (M-F 7am-4pm).
- We exclude any additional work required by authority having jurisdiction.
- We exclude any cutting, patching, or painting and trenching/backfilling.

For Napa Electric:

Brandon De Lago

Brandon De Lago

I, the undersigned, authorize the work described above, to be installed and paid for subject to the conditions listed below.
 Terms as follows: At completion of work

Signature of Buyer: _____

(Please sign original and return: keep copy for your records)

8-22-19