

Detailed Scope of Work Horace Mann School

The following to be completed for the start of school August 2016.

- **Provide and install in 18 classrooms backpack shelf and hooks per attached photos and cut sheet. Attachment per provided detail not to exceed 7' of shelf per room, each to accommodate up to 30 hooks. Shelf color to be Black.**
- **In the multi purpose room, Provide and install in 4 locations temporary walls closing off "Aerobics Room" and "Fitness Room". Walls to be typical framing covered on both sides with tack board. Provide 1 door per room, standard 3'0 X 6'8 pre hung hollow core primed and painted. Provide and install typical ADA lever door hardware with lock and key.**
- **In the above rooms provide and install VCT tile floors, color to be selected by owner.**
- **Remove and re-install three (3) basketball poles and hoops, junior high school size and height appropriate, installed per manufactures requirements at east side of building "B". Location layout by owner TBD.**